




Solar 3.0 Defined

- An industry initiative to rapidly expand the market
- Earlier efforts focused on pre-requisites
 - Solar 1.0
 - 2006 2008
 - Policy focus
 - Solar 2.0
 - 2009 2010
 - Technology focus
- Solar 3.0 Outreach and Promoting best Practices
 - Identify inefficiencies and promote consistencies







Solar 3.0 2012 Goals


- Develop a comprehensive Solar 3.0 implementation plan
 - Motivate adoption of optimal permitting and inspection practices by code officials and related stakeholders
 - Increase awareness of tools, standards, and guidelines by 50%
 - Achieve 30% Solar 3.0 Tool Kit adoption by code officials in the targeted communities
- Select Top 100 communities for maximum adoption
 - Communities will receive in-person and online workshops at no cost to implement Solar 3.0 toolkits
 - Communities will be coached and evaluated for "Solar readiness"
- Establish <u>www.Solar30.org</u> as a clearinghouse of expert information on solar PV system deployment best practices



Solar 3.0 Cost Reduction Tools

- Solar 3.0 Resource Toolkit
 - Industry best practices
 - Comprehensive curriculum
 - Metrics & dashboards
- National Outreach
 - State
 - Metro region
 - City
- Stakeholder Education
 - Cities
 - Utilities
 - PV industry





Accomplishments To Date

- Solar30.org web site & tool kit
- Survey of installation practices
- PV Online Training joint development
- Companion course development
- California Guidebook contributions
- Baseline metrics analysis
- Events program started

PV Online Training Objective - Training uses DOE's NTER online training platform To educate code officials in using Training to be available in May proper methods for: An information button or "i- Inspecting residential solar PV button" references the National installations Electrical Code. Detecting common installation Hands-on companion mistakes workshops are being planned Applying an expedited permit by Regional Training Providers process and SolarTech's 3.0 initiative 13

PV Online Training for Code Officials

Modules

- 1. Roof Mounted Arrays and Wire Management
- 2. Electrical: Roof and Ground Mounted
- 3. Ground Mounted Arrays
- 4. Appropriate Signs
- 5. Equipment Ratings
- 6. Expedited Permit Process

This content will be presented via text, drill-down information, and a variety of media including still photos, videos, and selected 3D models.

Capstone

- How to Identify Solar Installation Problems
 - This will be an immersive, highly interactive lesson using 3D models and game-based interaction techniques.





5. Equipment Ratings

Photovoltaic Online Training

i © @ ← + →

Page 2 of 6

Topic 2: Junction Boxes

Key Points:

Emotion bases should be installed in complexes, with their barry embedding
Emotion bases installed in complexes, with their barry embedding
Emotion bases installed in complexes aread by naive obtaining work or waterpreaf and it, where near not prices should be complexed in a Emotion base.
The prior barriers of the observement of the prior facebox of the complexes.

Common Installation Wistakes;

Country hour or conduct holds reading them needy however the for source.
Using improper hitting is doing conservation we need no count.
Safety hour is a site in the angle will be in the first induces.
Using simplement in statical sources.
Excerpt will be induced angle the its not safety tradeat.

SunShot





PV Installation Concerns

- Utility compatibility and interaction
- Environment (e.g. indoor, rainproof, corrosion resistant)
- Maximum number of modules
- Fire exposure ratings
- · Location on roof

•

- Effect on roof covering
- Wind and snow loading


20

 \bigcirc

Items needed to Inspect PV?

- Permits
- Plans
- Wiring
- Attachment
- Equipment

23



Plans - Electrical (cont.)

- Electrical plan should be submitted that includes the following:
 - Make and model of modules, inverter(s) and/or combiner box if used
 - If batteries are to be installed include them in the diagram and show there locations and venting
 - Equipment cut sheets including inverters, modules, AC and DC disconnects and combiners

25

Plans - Electrical (cont.)

•

- Electrical plan should be submitted that includes the following:
 - Labeling of equipment as required by Article 690 and Article 705
 - Site diagram showing the arrangement of panels on the roof or ground, north arrow, lot dimensions, and the distance from property lines to adjacent buildings/structures (existing and proposed)

4

Plans - Structural

- Structural plan identifying support information for roof mounted systems including the following:
 - The type of roof covering and the number of roofing layers installed
 - Type of roof framing, size of members and spacing
 - Weight of panels, support locations and method of attachment

24

 \bigcirc

27

Plans - Structural (cont.)

•

- Structural plan identifying support information for roof mounted systems including the following:
 - Framing plan and details for any work necessary to strengthen the existing roof structure
 - Any relevant calculations (when required)
 - Location of PV equipment on the building

Plans - Structural (cont.)

- Structural plan identifying support information for roof mounted systems including the following:
 - Where an approved racking system is used...
 - provide documentation showing the manufacturer of the rack system
 - maximum allowable weight the system can support
 - attachment method to the roof or ground
 - product evaluation information or structural design for the rack system

26

 \bigcirc

29

Plans - Code Requirements

• Site Plan –


NEC 80.21 (Annex H), IBC 107.2.5, IRC R106.2

- One-Line Diagram NEC 215.5
- Attachment Details NEC 110.3(B), IBC 107.2.1, IRC R106.1.2
- Equipment Specifications –


NEC 690.4(D), IRC R905.16.1, IRC R905.16.3, IRC M2302.3, IRC M2302.4, IBC 1505.8, IBC 1507.17.1, IBC 1507.17.3, IBC 1509.7.2, IBC 1509.7.4 (4)

Attachment

- The International Building Code (IBC) Section 106.3 Load Supports
- Dead loading and wind loading of roof are covered in IBC 1603.1.4, 1603.1.8, 1604.2, 1606,2



33



Key Inspection Points

- Number of PV modules and PV model numbers match plans
- Array conductors and components are installed in a neat and workman like manner
- PV array is properly grounded

•

- Electrical boxes are accessible and connections are suitable for environment
- Array is fastened and sealed according to attachment detail
- Conductors ratings and sizes match plans


Key Inspection Points (cont.)

- Appropriate signs are properly constructed, installed and displayed, including:
 - Sign identifying PV power source system attributes at dc disconnect
 - Sign identifying ac point of connection
 - Sign identifying switch for alternative power system

$^{\textcircled{0}}$ Key Inspection Points (cont.) $^{\textcircled{0}}$


- Equipment ratings are consistent with application and installed signs on the installation, including:
 - Inverter has a rating as high as max voltage on PV Power Source sign
 - DC-side OCPD's are DC rated at least as high as max voltage on sign
 - Switches and OCPDs are installed according to manufacturers specifications


34



Key Inspection Points (cont.)

- Equipment ratings are consistent with application and installed signs on the installation, including:
 - Inverter is rated for the site ac voltage supplied and shown on the ac point of connection sign
 - OCPD connected to the ac output of the inverter is rated at least 125% of maximum current on sign, and is no larger than the maximum OCPD on the inverter listing label
 - Sum of the main OCPD and the inverter OCPD is rated for not more than 120% of the busbar rating






Solar 3.0 Event Schedule


- Workshops (with CEU's)
 - July 24 Boston, MA
 - August 28 Plano, TX
 - Sept 26 Phoenix
 - Oct 11 Madison, WI
 - Nov 16 San Francisco, CA
 - Oct/Nov NY/NJ
- Outreach
 - July 11 San Francisco, CA
 - Oct XX Washington, DC
 - Sept 10 Orlando, FL

Get Involved Solar 3.0

- Come to <u>www.solar30.org</u>
 - Sign up for news
 - Complete your community or utility profile
 - Explore best practices in Permitting
- Join Solar 3.0 on LinkedIn
- See how Solar 3.0 can benefit your community















Solar 3.0 – Key Metrics from Code Officials and Local Governments


Recent surveys conducted by the International Association of Electrical Inspectors (IAEI) and ICMA of code officials and local governments have highlighted a number of issues in the realms of permitting, inspection, and interconnection for the Solar 3.0 team to address. They include:

- · In most jurisdictions, permits have to be obtained in person.
- Coordination between non-municipal utilities and authorities having jurisdiction is limited.
- · Few local governments engage in solar education campaigns.
- A vast majority of local governments do not offer expedited or streamlined permitting processes for standard PV systems.
- Most jurisdictions do not make solar permitting information or fee schedules available online.
- A major lack of training amongst both code officials and solar installers exists.



Solar 3.0 – Key Metrics from Code Officials

A recent survey of the International Association of Electrical Inspectors determined that a lack of training amongst both inspectors and the solar industry is the single largest barrier to more efficiency in permitting, inspection, and interconnection of rooftop solar PV systems.



Solar 3.0 – Key Metrics from Local Governments

Financial and customer acquisition issues are a major component of non-hardware balance of system costs. Solar 3.0 will also track key metrics in these areas using iterative ICMA surveys as they become available.

Metric % of jurisdictions reporting existence of bulk purchasing/solarize and/or customer aggregation programs.	2011 Survey Result 8%
% of jurisdictions reporting that third party financing is available.	35% yes, 23% no, 42% unsure
% of jurisdictions with an active community solar program.	2%, 5% in progress

